

प्रेषण

नितेश कुमार झा  
अपर सचिव  
उत्तराखण्ड शासन

प्राप्त

निदेशक  
आई0टी0डी0ए0  
93, फेरा-II  
वसुन्त विहार  
देहरादून

सूचन प्रौद्योगिकी विभाग

देहरादून: दिनांक 23 नवम्बर 2009

विषय— स्वान योजना के अन्तर्गत जनपद हरिद्वार में स्थापित विभिन्न नैटवर्क केन्द्रों पर आवश्यक अतिरिक्त कार्य हेतु धनराशि की स्वीकृति के सम्बन्ध में।

सहोदय,

कृपया जिलाधिकारी हरिद्वार के पत्र संख्या 579/नाजिर सदर— 2009 दिनांक 23.10.2009 का संदर्भ ग्रहण करने का कष्ट करें। उक्त पत्र के माध्यम से स्वान योजना के अन्तर्गत जनपद हरिद्वार में स्थापित विभिन्न नैटवर्क केन्द्रों पर आवश्यक अतिरिक्त कार्य हेतु धनराशि रु0 0.73 लाख के आगणन शासन में प्राप्त हुए। शासन में प्राप्त उक्त आगणनों का परीक्षण टी0ए0सी0 वित्त विभाग से कराया गया। टी0ए0सी0 वित्त विभाग द्वारा परीक्षणोपरान्त धनराशि रु0 0.73 लाख के सापेक्ष धनराशि रु0 0.73 लाख पर अपनी स्वीकृति प्रदान की है।

उक्त स्वीकृति निम्न प्रतिबन्धों के साथ प्रदान की जाती है।

- I. कार्य करने से पूर्व मदवार दर विश्लेषण विभाग के अधीक्षण अभियन्ता द्वारा स्वीकृत/अनुमोदित दरों के आधार पर तथा जो दरें शेड्यूल ऑफ रेट्स में स्वीकृत नहीं है अथवा बाजार भाव से ली गयी हो, की स्वीकृति नियमानुसार अधीक्षण अभियन्ता से अनुमोदन करना आवश्यक होगा।
- II. कार्य करने से पूर्व विस्तृत आगणन/मानचित्र गठित कर नियमानुसार सक्षम प्राधिकारी से प्राविधिक स्वीकृति प्राप्त करनी आवश्यक होगी।
- III. कार्य पर उतना ही व्यय किया जाये जितनी राशि स्वीकृत की गयी है। स्वीकृत धनराशि से अधिक व्यय कदापि न किया जाय।

- vi. एक मुश्त प्रविधानों को कार्य करने से पूर्व विरत आगणन गठित कर राक्षम अधिकारी से अनुमोदन प्राप्त कर लिया जाय।
- vii. कार्य करने से पूर्व समस्त औपचारिकतायें तकनीकी दृष्टि को मध्यनजर रखते हुए एवं लो0नि0वि0 द्वारा प्रचलित दरों/विशिष्टियों को ध्यान में रखते हुए निर्माण कार्य को सम्पादित करना सुनिश्चित करें।
- viii. कार्य करने से पूर्व उच्चाधिकारियों एवं भूगर्भवेत्ता से कार्य स्थल का भली-भाँति निरीक्षण अवश्य करा लिया जाय तथा निरीक्षण के पश्चात दिये गये निर्देशों के अनुरूप ही कार्य कराया जाय।
- ix. निर्माण सामग्री को उपयोग में लाने से पूर्व सामग्री का परीक्षण प्रयोगशाला से अवश्य करा लिया जाय तथा उपयुक्त सामग्री को ही प्रयोग में लाया जाय।
- x. मुख्य सचिव, उत्तराखण्ड शासन के शासनादेश संख्या 2047/XIV-219(2006) दिनांक 30.05.2006 द्वारा निर्गत आदेशों का कार्य कराते समय या आगणन गठित करते समय कड़ाई से पालन करने का कष्ट करें।
- xi. आगणन गठित करते समय तथा कार्य प्रारम्भ कराने से पूर्व Uttarakhand Procurement Rules 2008 का अनुपालन सुनिश्चित किया जाय।
2. इत संबंध में मुझे यह कहने का निदेश हुआ है कि कृपया जिलाधिकारी हरिद्वार को स्वयं योजना हेतु उक्त वर्णित कार्य के लिये धनराशि रू0 0.73 लाख अवमुक्त करने का कष्ट करें।
3. टी0ए0सी0 द्वारा परीक्षणोपरान्त उपलब्ध करायी गयी आख्या संलग्न कर प्रेषित की जा रही है।

संलग्नक:- यथोक्त

भवदीय  
(नितेश कुमार झा)  
अपर सचिव

संख्या प्र0स/192/XXXIV/सू0प्रौ0/2008 तदिनांकित  
प्रतिलिपि निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

1. जिलाधिकारी, हरिद्वार।
2. राज्य सूचना अधिकारी, एन0आई0सी0, सचिवालय परिसर, देहरादून।
3. मार्ट फाइल।

आज्ञा से  
(हरिओम)  
संयुक्त सचिव

# BILL OF QUANTITIES

कार्य का नाम प्रधान योजना के अन्तर्गत, जनपद हरिद्वार में स्थापित विभिन्न नेटवर्क केन्द्रों पर आवश्यक अतिरिक्त कार्य।

Sl No.	Particulars of Work	Qty.	Unit	Rate per unit (in Rs.)	Amount (in Rs.)
1	First Class Brick work (one brick thick) in 1:6 cement and fine sand of 1:25 F.M. mortar in superstructure	5.01	cu. m.	2999.00	15024.99
2	10 mm thick plaster with cement and Fine Sand of 1:25 F.M. mortar in 1:6 (Plain surface)	21.78	sq. m.	80.85	1760.913
3	12 mm thick plaster with cement and Fine Sand of 1:25 F.M. mortar in 1:6 (Rough surface)	21.78	sq. m.	88.60	1929.71
4	White Wash (3 coats)	22.50	sq. m.	7.05	158.63
5	Painting or varnishing on iron works in small areas or new wood work with one coat of ready priming paint and two coats of approved superior quality ready mixed paint of clear synthetic varnish, including supply of all materials, labour and T&P etc. required for proper completion of work	32.22	sq. m.	55.15	1776.93
6	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade - New Work (two or more coats) over and including priming coat with cement primer	51.66	sq. m.	41.55	2146.47
7	Dismantling doors, windows, including chowkhats, with hold -fast and including stacking of materials as directed by the Engineer-in-charge within a distance of 60 m	4.05	sq. m.	31.00	125.55
8	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6, painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead (for door & window chowkhats)	1.00	Nos.	354.45	354.45
9	Supply & Fixing of 32 mm Commercial Quality approved Plywood flush Door Shutter	5.67	sq. m.	850.00	4819.50
10	Supply & Fixing of Aluminium Fittings with screw for Doors & Windows	5.67	sq. m.	120.00	680.40
11	S/F of vinyl flooring i/c adhesive: labour, material incl. all	24.30	sq. m.	405.00	9841.50
12	P/F in position collapsible steel shutters with vertical channels 20 x 10 x 2 mm and braced with flat iron diagonals 20 x 5 mm size with top and bottom rails of T iron 40 x 40 x 6 mm with 38 mm dia steel pulleys with bolts, nuts locking arrangement, stoppers, handles, complete including applying a priming coat of approved red lead paint	10.44	sq. m.	3127.00	32645.88
13	P/F pressed steel door frames confirming to IS: 4351 manufactured from commercial mild steel sheet of 1.25 mm thickness including hinges jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50 x 25 mm or base ties of 1.25 mm pressed mild steel welded or rigidly fixed together by mechanical means, adjustable lugs with split end tail to each jamb including steel butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge	8.20	m	251.90	2065.58
<b>Total Amount (in Rs.)</b>					<b>73330.50</b>

### SUMMARY OF ESTIMATED COST

कार्य का नाम स्वयं योजना के अन्तर्गत, जनपद हरिद्वार में स्थापित  
विभिन्न नेटवर्क केन्द्रों पर आवश्यक अतिरिक्त कार्य।

Sl. No.	Sub - Head	Amount (in Rs.)
1	Estimated Cost (As per Bill of Quantities)	73330.50
	Total Amount	73,330.50
	Say (in Rs.)	0.73 lacs

J.E. / R.E.S.

A.E. / R.E.S.

*Per*  
Executive Engineer  
Rural Engineering Service  
Haridwar